

# Addendum

No. TWO Date: 9.6.18

Project: SECURITY VESTIBULES AT VARIOUS SCHOOLS  
FOR  
THE CHILTON COUNTY BOARD OF EDUCATION  
CLANTON, ALABAMA

PROJECT NO. 18-143

## A2.1 GENERAL

- A. The following changes and/or substitutions to the plans and specifications are hereby made a part of same and are incorporated in full force as part of the contract.
- B. Bidders shall acknowledge receipt of this Addendum in writing on his Proposal Form.

## A2.2 SPECIFICATIONS

- A. See the following responses to RFI questions received from Contractor's

**Question:**

The new hollow metal units appear to be at interior locations. Do we need to add the excess cost to hot dip galvanize the hollow metal?

**Answer:**

Delete the requirement to hot dip galvanize new hollow metal frames.

**Question:**

Is all new glass to be bullet resistant?

**Answer:**

- a. Doors, view panels and pass windows to have bullet resistant glass as specified.
- b. Transoms above door height to have tempered glass as specified.
- c. Sidelights to have metal panels as specified.

**Question:**

Clarify scope of work for note "Provide slot at bottom of glass."

**Answer:**

Modify existing hollow metal storefront with an additional horizontal member to provide a 3 inch high pass-thru slot where shown. Cut existing glass to fit and verify slot location with owner.

A2.3 DRAWINGS - NONE

END OF ADDENDUM TWO