

Addendum

No. ONE Date: 4.26.18

Project: REROOFING CURRY MIDDLE SCHOOL
FOR
THE WALKER COUNTY BOARD OF EDUCATION
JASPER, ALABAMA

PROJECT NO. 18-135
BC # 2018184

A1.1 GENERAL

- A. The following changes and/or substitutions to the plans and specifications are hereby made a part of same and are incorporated in full force as part of the contract.
- B. Bidders shall acknowledge receipt of this Addendum in writing on his Proposal Form.

A1.2 SPECIFICATIONS

- A. Refer to **Section 07500, Membrane Roofing**, clarifications as follows:

Clarification: Where existing roof deck is lightweight concrete decking, remove existing BUR system down to the lightweight concrete deck.

Clarification: Where existing roof deck is metal decking, remove existing BUR system down to metal deck.

Clarification: Install air barrier material over existing metal decking, equal to Vapair Seal MD.

Clarification: Tapered insulation is not required where adequate roof slope exists in the existing structure. New insulation is to meet the minimum total R value of **25**.

- B. The following manufactures are hereby approved subject to the plans and specifications:

Section 07500, Membrane Roofing (EPDM):

Johns Manville

A1.3 DRAWINGS- NO CHANGES

END OF ADDENDUM ONE